

S.C. MAD - CONS S.R.L.
Mun. Campulung Mold., Jud. Suceava
C.U.I. NR. 17385327
NR. J33/444/21.03.2005
TEL. MOB. 0740231628



**DEVIZ ESTIMATIV LUCRARI
DE REPARATII GRUPURI SANITARE - SCOALA GENERALA CU
CLASELE I - VII - ARGEL
Com. Moldovita, jud. Suceava**

NR. CRT.	DENUMIRE ARTICOL CANT+UM	PREȚ UNITAR	MAT.	MAN.	UTILAJ	TOTAL
1.	Desfacere pereti la Wc-uri individuale 21,60 mp					
2.	Desfacere pardoseli din gresie 31,50 mp					
3.	Desfacere grinzi de sub pardoseala 31,50 mp					
4.	Demontare wc-uri cu rezervor pe vas 5 buc					
5.	Demontare lavoare 3 buc					
6.	Umplutura din balast 31,50 mc					
7.	Turnare placa din beton armat cu g =10 cm 3,15 mc mp					
8.	Armatura din plasa de sarma la placa 192 kg					

9.	Sapa din mortar de ciment 31,5 mp					
10.	Montare pardoseala din gresie 31,50 mp					
11.	Montare pereti din pvc la wc-uri individuale 21,60 mp					
12.	Montare usi interioare la Wc 5 buc					
13.	Montare WC -uri cu rezervor pe vas 5 buc					
14.	Demontat si montat pisoare individuale 2 buc					
15.	Montare lavoare existente cu robineti noi 5 buc					
16.	Refacere instalatie electrica interioara si montare 3 corpuri de iluminat inluorescente (neon)					
17.	Montare calorifere 5 buc					
18.	Zugraveli cu var lavabil la pereti si tavana 72,80 mp					
	TOTAL					

	TOTAL CHELT. DIRECTE					
	Cheltuieli aprovizionare si transport					
	Contributie asiguratorie pentru munca	2,25%				
	Chelt. indirecte					
	TOTAL DEVIZ					
	TVA	19%				
	Rotunjiri					
	TOTAL GENERAL DEVIZ					LEI

Valoarea totala a lucrarilor de reparatii
este de lei.

07.09.2020

INTOCMIT,
Sing.MIHAI FLOCEA

